

NO. 105

21505240000

CERTIFICATE

CERTIFIED LAND CORNER

SE-Cor., 24-15-5.

105
No. 93

21505240000



Bryan H. Meyer
H. A. Sime and Associates
P. O. Box 50
Tomah, Wisconsin 54660
Phone: (608)-372-5392

I, Bryan H. Meyer, do hereby certify that on the 30th day of October 1997, I found (evidence) ~~(no evidence)~~ of the Southwest corner of Section 19, T 15 N, R 4 W Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

Dated this 21st day of Jan. 1998.

Bryan H. Meyer
Deputy County Surveyor
Title

History of corner establishment since Original Government Survey

Monroe County Surveyor, Fred A. Holden was at this corner in April of 1905 while doing work in Section 19. No recorded history was found in the LaCrosse County Records.

Description of corner evidence found:

I found a sturdy three-way fence corner. I spoke with Mr. Andrew Steenberg, long-time local resident and adjoining land owner. He stated that the three-way fence corner was at its present location for as long as he could remember. Based on this witness testimony and my measurements, I accepted the three-way fence intersection as the corner.

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:

Crew: B. Meyer, D. Malliet
Date: October 30, 1997 - 11:15 a. m.
Weather: Overcast, 45°±
Witnesses to corner location:

Bryan H. Meyer

Douglas J. Malliet

WITNESS:

Set 1" x 25" round iron bar. hay field

WITNESS:


Set 1 1/8" x 28" iron shaft.



MONUMENT:

Set cast iron Harrison marker, up 2"±.
Set sign on metal post 0.5' South of Harrison.

NOTE: The bearings shown hereon are magnetic hand compass bearings.



WITNESS:

14" White Oak

WITNESS:

16" White Oak


WISCONSIN COORDINATE SYSTEM

SURVEY CONTROL ORDER

Horizontal	_____
Vertical	_____

Corner	East (X)	North (Y)	Elevation (Z)	Zone
Control Sta. Name				

TO REACH: Get permission from Mr. Andrew Steenberg. Take field road South of C.T.H. "H"; starts ESE of Steenberg residence - runs Southerly to East-West fence; follow fence West to corner.



City, Village or Town of Portland

County of Monroe

COUNTY SURVEYOR FORM NO. 1