


21506292000

U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 29 T 15 N, R 6 W, TOWN OF GREENFIELD
LA CROSSE COUNTY

LOCATION OF LANDMARK

CREW: SD

JC

DATE: 8/15/02

Describe any record evidence, monument evidence, testimonial evidence, or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

I found a 1" pipe at the corner location that was previously used. It was in the existing N-S fence line. I accepted it as the corner.

Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

None.

WISCONSIN COORDINATE SYSTEM

North

East

Theta Angle

Horiz. Order

Vert. Order


TYPE OF LANDMARK

FOUND 1" IP

BEARINGS ARE REFERENCED TO
THE SOUTH LINE OF THE SE 1/4,
SECTION 29 (ASSUMED EAST)


RECORD OF DURABLE WITNESS MONUMENTS

| NO | DESCRIPTION | BEARING | DISTANCE |
|----|---|---------|----------|
| 1 | 14" RED OAK (P.K. IN BASE & UNBLAZED) | N 0° E | 37.0' |
| 2 | 10" WHITE OAK (P.K. IN BASE & UNBLAZED) | S 87° E | 21.2' |
| 3 | 12" WHITE OAK (P.K. IN BASE & UNBLAZED) | S 2° W | 28.0' |
| 4 | 9" BLACK CHERRY (P.K. IN BASE & UNBLAZED) | S 50° W | 9.3' |




PLAN VIEW DRAWING OF REFERENCE TIES

MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER



I, Scott M. Dunnum

HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.



Scott M. Dunnum
 Signature

6/28/03
 Date

Seal