

21605240000

COUNTY SURVEYOR FORM NO. 1

CERTIFICATE

CERTIFIED LAND CORNER

Section 19-16-84  
Town, Bangor

No. 93

I, Bryan H. Meyer, do hereby certify that on the 27th day of July, 1984, I found (evidence) Section 19 of the Southwest corner of Section 19, T 16 N, R 4 W Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

Dated this 15th day of Oct., 1984.

Bryan H. Meyer  
Deputy County Surveyor  
Title

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:  
Crew: Meyer, Lund  
Date: July 27, 1984 - 1:30 P.M.  
Weather: P. Cloudy, Breezy, 70°±.  
Witnesses to corner location:

Bryan H. Meyer - R. L. S. 1712

James Lund


History of corner establishment since Original Government Survey

Henry I. Bliss, County Surveyor of Lacrosse County surveyed the entire Township of Bangor and set monuments at each Section and Quarter corner in 1867.

Description of corner evidence found:

I found a 6"x6" cut stone leaning badly at a two way fence corner. I spoke to Mr. Herbert Olson, a local land owner, and he told me the stone had been at this location for as long as he could remember. I therefore accepted the stone as the corner.



Note: The trees shown are double blazed; each distance shown is to a nail set in a hack in the side of each tree.



Reset 6"x6" stone at fence corner. This stone has numbers cut into each side. I set the stone so that the numbers are facing the corresponding sections. I set a 3/4"x24" round iron bar on the Northeast side of the stone. The stone is up 8"±.

WISCONSIN COORDINATE SYSTEM

SURVEY CONTROL ORDER	
Horizontal	
Vertical	
Corner	East (X)
Control Sta. Name	North (Y)
	Elevation (Z)
	Zone



Town of Leon  
County of Monroe