


21605250000

## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 25 T 16 N, R 5 W, TOWN OF BANGOR  
LA CROSSE COUNTY



LOCATION OF LANDMARK

CREW: **WILLIAM C. JUNG**  
**PETER F. FOLLANSBEE**  
DATE: **10/10/2000**

## WISCONSIN COORDINATE SYSTEM

North 667,236.946

East 1,728,123.428

Theta Angle

Horiz. Order

Vert. Order

DATUM: 83('91)

TYPE OF LANDMARK

3/4" x 30" IRON BAR.

BEARINGS ARE REFERENCED TO  
GRID NORTH AS PER SECTION DATA.

Describe any record evidence, monument evidence, testimonial evidence or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.


I set this corner on line between the NE of Section 25 and the E1/4 of Section 36 and also on line with the old line fence to the East. After surveying the County line, the sections to the West, and analyzing this data, this was in my opinion the best way to set this corner. To the South my distance fits the original government retracement distance within 9 inches.

Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

**NONE KNOWN.**

RECORD OF DURABLE WITNESS MONUMENTS  
MAGNETIC


NO	DESCRIPTION	BEARING	DISTANCE
1	SET A NAIL IN S.W.-SIDE OF A 14" OAK (UNBLAZED)	N 22° W	46.03 FT.
2	SET A NAIL IN S.-SIDE OF A 16" HICKORY (UNBLAZED)	N 79° E	SL. = 134.40'
3	SET A 1-1/4" IRON PIPE ON LINE WITH FENCE	EAST ±	79.18 FT.
4	P.K. NAIL SURVEY POINT IN CENTERLINE C.T.H. "J"	EAST ±	36.55 FT.



MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER

( GRID BEARINGS  
AND DISTANCES )


(not to scale)



I, WILLIAM C. JUNG, COUNTY SURVEYOR  
HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD  
WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND  
THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT  
AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

William C. Jung  
Signature

11/16/00  
Date



Seal