


21606302000

U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 29 T 16 N, R 6 W, TOWN OF Barre

LA CROSSE COUNTY



LOCATION OF LANDMARK

Crew: WILLIAM C. JUNG
PETER F. FOLLANSBEE

Date: 11/14/1991

Describe any record evidence, monument evidence, testimonial evidence or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

I found a stone at the corner and accepted it as the best available evidence of the original government corner position. Also found were both bearing trees, one alive and the other a stump.

Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

None known

WISCONSIN COORDINATE SYSTEM

North

East

Theta Angle

Horiz. Order

Vert. Order

TYPE OF LANDMARK


Existing 5" x 6" Stone

BEARINGS ARE REFERENCED TO

**RECORD OF DURABLE WITNESS MONUMENTS
MAGNETIC**

NO	DESCRIPTION	BEARING	DISTANCE
1	Set P.K. Nail in S.-side 22" W. Oak(Orig. B.T.)	N 89°W	18.76 Ft.
2	Set P.K. Nail in N.W.-side 14" Oak	N 27°E	16.28 Ft.
3	Set P.K. Nail in S.W.-side 3½" Cedar	S 52°E	4.24 Ft.
4	Set P.K. Nail in S.E.-side 11" W. Oak	S 29°W	20.23 Ft.

(Note: distances are measured to set P.K. Nails in hacks in B.T.'s that are double blazed except the Cedar which is unblazed. Nailed sign to Cedar.)



Scale: 1" = 15'


PLAN VIEW DRAWING OF REFERENCE TIES

MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER

No section measurements made by me at this time.

I, William C. Jung, Deputy County Surveyor
HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD
WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND
THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT
AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

William C. Jung December 5, 1991
Signature Date



Seal