


## U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 8 T 17 N, R 5 W, TOWN OF BURNS  
LA CROSSE COUNTY



LOCATION OF LANDMARK

## WISCONSIN COORDINATE SYSTEM

North 187216.03

East 513595.35

Theta Angle

Horiz. Order

Vert. Order

## TYPE OF LANDMARK

3/4" X 24" IRON BAR

BEARINGS ARE REFERENCED TO  
 LACROSSE COUNTY  
 COORDINATE SYSTEM

CREW: CF

TS KK

DATE: 2/10/06

Describe any record evidence, monument evidence, testimonial evidence, or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

In February of 2001 I was working in this area and established the SE corner of Section 8 and the S 1/4 corner of Section 9. I had a computed position for this corner.

I set this corner equidistant and on line from the NE & SE corners of Section 8.

Phil Farrington, the land owner, accompanied us to the corner location. He could not ever recall any type of occupation at this corner. The corner falls on a pastured knob with a number of birch trees growing nearby.

Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

None known.


FEB 21 2006

COUNTY SURVEYOR'S OFFICE

## RECORD OF DURABLE WITNESS MONUMENTS


NO	DESCRIPTION	BEARING	DISTANCE
1	3/4" IRON BAR 2'± FROM 8" BIRCH	S 53°10'30" W	39.82'
2	3/4" IRON BAR 2'± FROM 8" BIRCH	S 10°09'24" E	27.89'
3	3/4" IRON BAR 2'± FROM 8" BIRCH	N 45°02'24" W	40.59'
4	3/4" IRON BAR 2'± FROM APPLE TREE	N 44°51'38" E	26.89'

( NOT TO SCALE )



PLAN VIEW DRAWING OF REFERENCE TIES

### MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER



I, Christopher W. Fechner


HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*Christopher W. Fechner*

2/10/06

Signature

Date



Seal