


21706062000

U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 6 T 17 N, R 6 W, TOWN OF HAMILTON

LA CROSSE COUNTY



LOCATION OF LANDMARK

CREW: WILLIAM C. JUNG
 PETER F. FOLLANSBEE
 DATE: 5/19/1997

WISCONSIN COORDINATE SYSTEM

North

East

Theta Angle

Horiz. Order

Vert. Order

TYPE OF LANDMARK

BRASS CAP LUNDE MARKER.

BEARINGS ARE REFERENCED TO

Describe any record evidence, monument evidence, testimonial evidence or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

I accepted the old occupied corner as the best available evidence of the original government corner position and monumented it with a brass capped Lunde marker. This fence corner had been used as the corner in previous survey work.

Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

NONE KNOWN.

RECORD OF DURABLE WITNESS MONUMENTS

MAGNETIC


NO	DESCRIPTION	BEARING	DISTANCE
1	SET NAIL IN NW-SIDE 9-1/2" CHERRY	N 29°E	26.93 FT.
2	SET NAIL IN NW-SIDE 14-1/2" BIRCH	N 35°E	29.36 FT.
3	SET NAIL IN NW-SIDE 13" ASPEN	N 61°E	34.53 FT.
4	SET NAIL IN SW-SIDE 9-1/2" ELM	S 72°E	20.76 FT.

SCALE: 1" = 20'

(NOTE: THE 4 BEARING TREES ARE DOUBLE BLAZED)

(FIELD)

E. 1/4-COR., SEC. 6-17-6.
 SET A BRASS CAP LUNDE MARKER AT THE OLD FENCE CORNER AND MOUNDED IT WITH ROCKS. BURIED A WINE BOTTLE CONTAINING A SHELL CASING WITH THE MARKER AND SET A SIGN & POST NEARBY.



PLAN VIEW DRAWING OF REFERENCE TIES

MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER

No section measurements were made by me at this time.

I, WILLIAM C. JUNG, COUNTY SURVEYOR
 HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

William C. Jung 2/6/98
 Signature Date



Seal