


U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 13 T 17 N, R 6 W, TOWN OF HAMILTON  
 LA CROSSE COUNTY



LOCATION OF LANDMARK

Crew: William C. Jung  
 Peter F. Follansbee

Date: December 17, 1992

Describe any record evidence, monument evidence, testimonial evidence or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

I set the corner by single proportionate measurement and monumented the corner with a Lunde marker. A liquor bottle with a shell casing was buried by the Lunde, and a post with sign was set.


Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

None known.

WISCONSIN COORDINATE SYSTEM
North
East
Theta Angle
Horiz. Order
Vert. Order
TYPE OF LANDMARK
Brass capped Lunde marker
BEARINGS ARE REFERENCED TO
True

RECORD OF DURABLE WITNESS MONUMENTS

NO	DESCRIPTION	BEARING	DISTANCE
1	P.K. nail in unblazed 4" hickory	S41°W	10.05
2	" double blazed 15" hickory	N71°W	53.23
3	" unblazed 4" hickory	N64°E	18.91
4	" double blazed 8" hickory	S78°E	39.38




(not to scale)

PLAN VIEW DRAWING OF REFERENCE TIES

MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER

(not to scale)



I, William C. Jung, Deputy County Surveyor,  
 HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD  
 WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND  
 THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT  
 AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

William C. Jung  
 Signature

December 21, 1992  
 Date



Seal