


21807030000

U. S. PUBLIC LAND SURVEY MONUMENT RECORD

SECTION 2 T 18 N, R 7 W, TOWN OF Farmington

LA CROSSE COUNTY



LOCATION OF LANDMARK

WISCONSIN COORDINATE SYSTEM

North

East

Theta Angle

Horiz. Order

Vert. Order

TYPE OF LANDMARK

Set brass cap Lunde marker

BEARINGS ARE REFERENCED TO

Crew: WILLIAM C. JUNG

Date: 9/17/1991 & 3/26/07 (P and B)

Describe any record evidence, monument evidence, testimonial evidence or any other material evidence you considered and whether the monument was found or restored through acceptance of an obliterated evidence location.

I accepted the iron pipe at the occupied corner as the best available evidence of the original government corner position. This pipe had been used as the corner in previous surveys. I replaced the pipe with a brass capped Lunde marker. A whiskey bottle with a shell casing was buried on the SE side of the Lunde.


Describe or show any material discrepancy between the location of the restored corner and that of the corner previously restored or reestablished.

None known

RECORD OF DURABLE WITNESS MONUMENTS
MAGNETIC

NO	DESCRIPTION	BEARING	DISTANCE
1	Set P.K. Nail in N-side 10" Oak(sgl. blazed)	S 87 W	31.43 Ft.
2	Set P.K. Nail in NW-side 6" Norway(dbl. blz)	N 44 E	17.70 Ft.
3	Set P.K. Nail in 8" Norway w/sign (dbl. blz)	N 78 E	3.91 Ft.
4	Distance to center of 3" Oak(unblazed)	S 42 W	5.62 Ft.

S.W.-COR., SEC. 2-18-7.
 SET BRASS CAP LUNDE MARKER
 TO REPLACE AN EXISTING IRON
 PIPE. STEEL FENCE POST W/SIGN TO
 THE N.E. . BURIED A WHISKEY
 BOTTLE CONTAINING A SHELL
 CASING TO THE S.E. OF THE
 LUNDE MARKER.



PLAN VIEW DRAWING OF REFERENCE TIES

MAP SHOWING DISTANCE AND DIRECTION TO OTHER PUBLIC LAND SURVEY CORNERS USED FOR REESTABLISHING THE CORNER

No section measurements were made by me at this time. See section data of record.


I, William C. Jung, Deputy County Surveyor
 HEREBY CERTIFY THAT THE CORNER LOCATION SHOWN ON THIS RECORD
 WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND
 THAT THIS U. S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT
 AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

William C. Jung
 Signature

November 8, 1991

Date

Revised: 7/19/07 *weg*



Seal