

TREMPEALEAU COUNTY

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

QUARTER Corner common to Sections 16 & 21

T. 18 N., R. 8 W.

Type of monument 7/8" X30" REBAR WITH ALUMINUM CAP

Location indicated on sketch - -

16	16
21	21

Location Sketch

Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

ORIGINAL GOVERNMENT ACCESSORIES WERE SEARCHED FOR, BUT NOTHING WAS FOUND. OTHER MONUMENT EVIDENCE WAS SEARCHED FOR, BUT NONE WAS FOUND. U.S.E.O. DID NOT FIND ANY CORNER EVIDENCE AT THIS CORNER POSITION DURING THEIR 1932 SURVEY. IN 1992, S. SOLBERG EITHER FOUND OR SET A NAIL AT THE NORTHWEST CORNER OF GOVERNMENT LOT 5 OF SECTION 21-18-8. THIS WOULD BE THE NORTHEAST CORNER OF THE NORTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION 21-18-8. A 1" IRON PIPE WAS FOUND AT THE MATHEMATICAL LOCATION OF THIS 1/16TH CORNER, BASED ON S. SOLBERG INFORMATION. ACCORDING TO A CONVERSATION WITH ANOTHER SURVEYOR, THIS IRON PIPE WAS VERY RECENTLY SET IN PLACE OF A FOUND P.K. NAIL FOR A PENDING SURVEY. A POSITION FOR THIS QUARTER CORNER WAS DETERMINED BY HOLDING THE "DOUBLE OVER" OF LINE AND DISTANCE FROM THE NORTHWEST CORNER OF SECTION 21-18-8 AND THE FOUND 1" IRON PIPE AT THE NORTHEAST CORNER OF THE NORTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION 21-18-8. THIS POSITION FALLS APPROXIMATELY 4 FEET SOUTH OF AN EAST/WEST LINE OF STEEL FENCE POSTS. THIS POSITION MATCHES ORIGINAL GOVERNMENT DISTANCE TO THE NORTHWEST CORNER OF SECTION 21-18-8 BY LESS THAN 1 FOOT. IT MATCHES ORIGINAL GOVERNMENT DISTANCE TO THE NORTHEAST CORNER OF SECTION 21-18-8 BY LESS THAN 8 FEET. IT MATCHES THE SINGLE PROPORTIONATE POSITION BETWEEN THE NORTHEAST AND NORTHWEST CORNER OF SECTION 21-18-8 BY ABOUT 1 FOOT NORTH/SOUTH AND BY LESS THAN 4 FEET EAST/WEST. IT ALSO MATCHES AN OLD RIVER BANK ON THE WESTERLY SIDE OF THE BLACK RIVER REASONABLY WELL WITH ORIGINAL GOVERNMENT MEASUREMENT. THEREFORE, BELIEVING THIS POSITION, AS DESCRIBED, TO BE THE BEST AVAILABLE EVIDENCE OF THIS CORNER'S ORIGINAL LOCATION, A 7/8" X30" REBAR WITH AN ALUMINUM CAP WAS SET AND REFERENCED AS SHOWN BELOW.

Show a plan view drawing depicting the relevant monuments, providing reference ties to at least 4 witness monuments. Describe witness monuments. Show relationship to occupation.

o SET 5/8" X24" REBAR WITH PLASTIC CAP

4' SE OF 24" DOUBLE MAPLE

SURVEY SIGN POST
1' NORTH OF MON.

BEARINGS REFERENCED TO
THE TREMPEALEAU COUNTY
COORDINATE SYSTEM

LINE OF STEEL FENCE POSTS

LINE OF STEEL FENCE POSTS

2' SOUTH OF
STEEL FENCE
POST

2' SOUTH OF
8" HACKBERRY

3' NORTH OF
18" MAPLE



no scale

Corner Identifier number

76-312

Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing. Show the distances between the corner as restored or reestablished, and (1) the corner as restored or reestablished, and (2) to at least 2 of the witness monuments shown on the drawing.

NO MATERIAL DISCREPANCY WAS FOUND.

Was the corner restored through acceptance of (1) an obliterated evidence location, (2) a found perpetuated location, or (3) an existent corner location?

AN OBLITERATED EVIDENCE LOCATION.

Was the corner reestablished through lost corner proportionate methods? If so, show the method including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location.

NO.

Show the corner history of record in chronological order from Original Government Survey to present.

**ORIGINAL GOVERNMENT SURVEY - CYRUS WOODWORTH - SEPTEMBER 1847
SET QUARTER SECTION POST. MARKED TWO BEARING TREES.**

**UNITED STATES ENGINEER OFFICE - WIELDE - JULY 1932
SURVEYS FOR LOCK AND DAM SYSTEM ALONG THE MISSISSIPPI RIVER. TRAVERSES
THE NORTH LINE OF SECTION 21-18-8. NOTES DO NOT INDICATE FINDING ANY
CORNER EVIDENCE AT THE NORTH QUARTER CORNER OF SECTION 21.**

**PRIVATE LAND SURVEYOR'S RECORDS - S. SOLBERG - JANUARY 1992
SURVEYS PARCEL IN SECTION 21-18-8. MAP SHOWS FOUND NAIL AT THE NORTHWEST
CORNER OF GOVERNMENT LOT 5 OF SECTION 21. NO MENTION OF THE NORTH QUARTER
CORNER OF SECTION 21.**

**PRIVATE LAND SURVEYOR'S RECORDS - S. SOLBERG - JANUARY 1992
SURVEYS PARCEL IN SECTION 21-18-8. MAP SHOWS EITHER A FOUND NAIL OR A SET
P.K. NAIL AT THE NORTHEAST CORNER OF GOVERNMENT LOT 5 OF SECTION 21. NO
MENTION OF THE NORTH QUARTER CORNER OF SECTION 21.**

**PRIVATE LAND SURVEYOR'S RECORDS - S. SOLBERG - JUNE 1996
SURVEYS PARCEL IN SECTION 21-18-8. MAP SHOWS A FOUND P.K. NAIL AT THE
NORTHEAST CORNER OF THE NORTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION
21-18-8. NO MENTION OF THE NORTH QUARTER CORNER OF SECTION 21-18-8.**

I, JOSEPH P. NELSEN
certify that the corner location shown on this record
was determined by me or under my direction and control
and that this U.S. Public Land Survey Monument Record
is correct to the best of my knowledge and belief.

Joseph P. Nelsen 9-21-99
Signature Date

Affix Land Surveyor Seal

